

AMENDMENT OF SOLICITATION/CONTRACT (AGREEMENT)

SECTION I

Instructions to Offerors --- Amendment of Solicitation. The following instructions apply unless specified otherwise in an AAFES letter accompanying this amendment.

a. Offerors must acknowledge receipt of this amendment prior to the hour and date specified for receipt of proposals in the original solicitation, or the hour and date specified in this amendment if such has been amended. Offeror must acknowledge by one of the following means:

(1) By signing and returning all except one copy of this amendment;

(2) By acknowledging receipt of this amendment on each copy of the proposal submitted;

(3) By separate letter or telegram which includes a reference to the solicitation and amendment number.

b. Proposals must be based upon and refer to the solicitation as amended. Unless an acknowledgment of this amendment is received by the Contracting Officer before the hour and date specified for receipt of proposals, Offeror=s proposal may be considered nonresponsive.

c. If you desire to revise a proposal previously submitted, such revision must be received prior to the hour and date specified for receipt of proposals inclosed in a sealed envelope addressed to the issuing office, with the name and address of offeror and the solicitation number on the face of the envelope. Telegraphic proposals will not be considered unless authorized by the solicitation; however, proposals may be modified by telegraphic notice provided such notice is received prior to the time set for receipt of proposals. Telegraphic modifications should not reveal the amount of the original or of the revised proposal.

SECTION II

Instructions to Contractor --- Amendment of Contract.

Unless otherwise instructed, all except one copy of this Amendment are to be executed by a person authorized to bind the firm contractually and returned to the Contracting Officer. The effective date will be the date the amendment is signed in block 6 by the Contracting Officer or the date(s) indicated in block 4, whichever is later.

QUESTIONS AND ANSWERS

Q-1: Are Front Counter Equipment Items 19 shown on Drawing Sheet EQ-1.01, Interior Elevation 8, furnished with Mosaic Tile MT-1 and MT-2 preinstalled?

Response: Front Counter Equipment Items 19 have two separate décor panels with prefabricated frames, embossed Mosaic Tile face and purse rail with down lighting that are completely pre-finished and furnished by Duke manufacturing as an accessory part to the two “Cold Pan” Equipment units. These panels are shipped separately and easily field attached to the Equipment unit fronts by the Contractor. Contractor shall also connect wiring for down lighting.

DRAWINGS CLARIFICATIONS

1. Sheet E-2.01 – PARTIAL FLOOR PLAN-POWER, New Electrical Panel P2A Notes and Panel Schedule; Modify requirements currently indicated as follows:

Change panel P2A rating from 100A Main Breaker to 100A Main Lugs only.

Change panel labeling and branch circuit identifications from P2A to P1A.

- Panel P2A (P1A) feeder shall come out of existing panel P-1. Replace existing 50A/3P breaker, currently serving Robin Hood oven, with 100A/3P breaker for new panel P1A feeder.**

2. Sheet A-1.01 – FLOOR PLAN/REFLECTED CEILING PLAN, Reflected Ceiling Plan Drawing; Add the following and make the following modification:

Add a 2 x 4 grid troffer with Emergency Standby Ballast, as shown on Sheet E-1.01, between 2 x 4 grid troffers and move Titus TMS-AA SA Diffuser and related accessories one ceiling grid space toward Serving Counter (west).

3. Sheet EQ-1.01 – EQUIPMENT LAYOUT, SCHEDULE & INTERIOR ELEVATIONS, Subway Equipment Schedule, Equipment Layout Plan and Interior Elevation 5; Delete the following:

Delete Equipment Item Number 23, Safe from Schedule, Plan and Elevation. This Item will not be included in the AF/CI Equipment Package.

4. Sheet EQ-1.01 – EQUIPMENT LAYOUT, SCHEDULE & INTERIOR ELEVATIONS, Subway Equipment Schedule, Item Number 27, Bread Oven, Plumbing Column; Delete N/A and add the following Plumbing requirement:

Equipment Item 27-Plumbing: ½” Cold Water (CW) supply will be required from existing CW piping in wall behind oven. Provide rough-in, shut-off valve and make final connections.

5. Sheet P-1.01 – PARTIAL FLOOR PLAN, NOTES, & SCHEDULES-PLUMBING, Partial Floor Plan-Plumbing and Plumbing Fixture Schedule; Add the following Plumbing requirement:

Add rough-in for ½” Cold Water (CW) supply line to Equipment Item 27, Bread Oven, from existing CW piping in wall behind oven. Provide rough-in, shut-off valve and make final connections.

6. Sheet E-2.01 – PARTIAL FLOOR PLAN-POWER, Subway Schedule and Partial Floor Plan-Power; Delete the following:

Delete Equipment Item Number 23, Safe. This Item will not be included in the AF/CI Equipment Package.

7. Sheet E-2.01 – PARTIAL FLOOR PLAN-POWER, Partial Floor Plan-Power; Add the following modifications:

Extend Circuit 1a to connect to front décor panel lighting furnished by equipment manufacturer (AF/CI) with two (2) Equipment Items 19.

Add one junction box and connection for Item 29a, Menu Board, on east wall for the third section of Menu Board with light.

Cash register outlet at south end of Serving Counter shall consist of a 6” x 6” x 4” box and 1” conduit stubbed from 22” rough-in height to above accessible ceiling.

Telephone outlet at south end of Serving Counter shall consist of a 4” x 4” square box and 1” conduit stubbed from 22” rough-in height to above accessible ceiling.

Relocate power, cash register and data outlets below Serving Counter mounted to west stainless steel surface inside Cashier Counter casework.